WINDOW SCHEDULE			
NUMBER	QTY	SIZE	DESCRIPTION
W01	1	0808	FIXED GLASS
W02	1	10030	TRIPLE CASEMNT-LHL/RHR
W03	1	1450	FIXED GLASS
W04	2	2020	DBL CASEMENT-LHL/RHR
W05	2	2070	FIXED GLASS
W06	3	3050	DBL CASEMENT-LHL/RHR
W07	4	3070	FIXED GLASS
W08	1	4060	DBL CASEMENT-LHL/RHR
W09	3	3060	DBL CASEMENT-LHL/RHR

DOOR SCHEDULE				
NUMBER	QTY	SIZE	DESCRIPTION	COMMENTS
D01	1	2068	HINGED-AT-GLASS	
D02	1	2068	HINGED-DEFAULT	
D03	2	2668	EXT HINGED-DEFAULT	
D04	3	3070	EXT HINGED-GLASS	
D05	1	3070	EXT HINGED-DEFAULT	
D06	1	3668	HINGED-AT-GLASS	
D07	1	4868	BIFOLD	
D08	2	6068	BIFOLD	
D09	1	6070	EXT HINGED-GLASS	
D10	1	2468	BIFOLD	
D11	6	2668	HINGED-DEFAULT	
D12	1	3070	HINGED-DEFAULT	

NOTE:

PROVIDE AN ESCAPE OR RESCUE WINDOW IN EACH BEDROOM THAT INCORPORATES THE FOLLOWING (CBC SECT. 310.4):

A MIN NET CLEAR OPENABLE AREA OF 5.7 SQ. FT.

A MIN NET CLEAR OPENING 20" IN WIDTH X 24" IN HEIGHT.

A MAX FINISHED SILL HEIGHT OF 44" ABOVE FLOOR.

NOTE:
PROVIDE BACKFLOW PREVENTION DEVICE FOR HOSEBIBS AND SPRINKLERS



MAIN HOUSE FLOOR PLAN

REVISIONS	BY
12/14/2011	1

DEXIGN SYSTEMS
P.O. BOX 3881 SANTA BARBARA, CA 93130 (805) 682-8723

A | I
B | D

©DEXIGN SYSTEMS 2011

NOTE: THESE DRAWINGS ARE BASED ON THE MOST ACCURATE INFORMATION AVAILABLE AT THE PRESENT TIME. DEXIGN SYSTEMS DOES NOT WARRANT OR GUARANTEE THE ACCURACY AND/OR COMPLETENESS OF THE WORK PRESENTED HEREIN BEYOND A REASONABLE DILIGENCE. IF ANY INSTANCES, DIMENSIONS OR DISCREPANCIES ARE FOUND ON THESE DRAWINGS, DEXIGN SYSTEMS WILL BE PROMPTLY NOTIFIED SO THAT DEXIGN SYSTEMS MAY ATTEMPT TO RESOLVE THEM.

THE LARRALDE RESIDENCE &
GUEST HOUSE
2169 REFUGIO ROAD
SANTA BARBARA, CA 93117

MAIN HOUSE FLOOR PLAN

Date	12/14/2011
Scale	1/4"= 1'-0"
Designer	
Job	LARRALDE
Sheet	5